2 PHASE AA – FIRST FLOOR DEMOLITION PLAN – AREA A.1
1/8" = 1'-0"

1 PHASE AA – FIRST FLOOR DEMOLITION PLAN – AREA A.2
1/8" = 1'-0"

- REMOVE ALL PIPE INSULATION VIA NJAC 5:23-8.17/8.19
- REMOVE ALL PIPE INSULATION VIA NJAC 5:23-8.17/8.19 & REMOVE FLOOR TILE VIA NON-FRIABLE METHODS
- REMOVE PIPE INSULATION & TANK INSULATION VIA NJAC 5:23-8.19
- REMOVE FLOOR TILE VIA NON-FRIABLE METHODS
- REMOVE TRANSITE PANELS ABOVE LOCKERS VIA NON-FRIABLE METHODS
- REMOVE FIRE DOORS VIA NON-FRIABLE METHODS

**NOTE:**

**SERVER ROOM TO REMAIN ACTIVE DURING ALL DEMOLITION AND ABATEMENT ACTIVITIES. THIS ROOM CONTAINS SENSITIVE ELECTRONIC COMPONENTS THAT NEED TO BE PROTECTED FROM DEBRIS AND DUST. STRICT PROTECTION GUIDELINES MUST BE FOLLOWED.**

| | | | | |
|---|---|---|---|---|
| TTI Environmental, Inc. www.ttienv.com | WILLIAM PATERSON UNIVERSITY HUNZIKER WING 1ST FLOOR 300 Pompton Road, Wayne, NJ | SCALE NTS | DRAWN BY DC | DATE 09/2015 |
| | | PROJECT 14-1532 | APP'D BY JS | DRAWING NO ASB-1 |

2 PHASE AA – SECOND FLOOR DEMOLITION PLAN – AREA A.1
1/8" = 1'-0"

1 PHASE AA – SECOND FLOOR DEMOLITION PLAN – AREA A.2
1/8" =

- REMOVE ALL PIPE INSULATION VIA NJAC 5:23-8.17/8.19
- REMOVE ALL PIPE INSULATION VIA NJAC 5:23-8.17/8.19 & REMOVE FLOOR TILE VIA NON-FRIABLE METHODS
- REMOVE FLOOR TILE VIA NON-FRIABLE METHODS
- REMOVE TRANSITE PANELS ABOVE LOCKERS VIA NON-FRIABLE METHODS
- REMOVE FIRE DOORS VIA NON-FRIABLE METHODS

| | | | |
|---|---|---|---|
| TTI Environmental, Inc. www.ttienv.com | WILLIAM PATERSON UNIVERSITY HUNZIKER WING 2ND FLOOR 300 Pompton Road, Wayne, NJ | SCALE NTS | DRAWN BY DC | DATE 09/2015 |
| | | PROJECT 14-1532 | APP'D BY JS | DRAWING NO. ASB-2 |

2 PHASE AA – THIRD FLOOR DEMOLITION PLAN – AREA A.1
1/8" = 1'-0"

1 PHASE AA – THIRD FLOOR DEMOLITION PLAN – AREA A.2
1/8" = 1'-0"

- REMOVE ALL PIPE INSULATION VIA NJAC 5:23-8.17/8.19
- REMOVE FLOOR TILE VIA NON-FRIABLE METHODS
- REMOVE TRANSITE PANELS ABOVE LOCKERS VIA NON-FRIABLE METHODS
- REMOVE FIRE DOORS VIA NON-FRIABLE METHODS

| | | | |
|---|---|---|---|
| TTI Environmental, Inc. www.ttienv.com | WILLIAM PATERSON UNIVERSITY HUNZIKER WING 3RD FLOOR 300 Pompton Road, Wayne, NJ | SCALE NTS | DRAWN BY DC | DATE 09/2015 |
| | | PROJECT 14-1532 | APP'D BY JS | DRAWING NO. ASB-3 |

**LEGEND**

- REMOVE DUMB WAITER INSULATION VIA NJAC 5:23-8.19
- REMOVE ALL PIPE INSULATION VIA NJAC 5:23-8.17/8.19
- REMOVE & REPLACE DRYWALL THAT CONTAINS VISIBLE MOLD IN ROOM 002 IN ACCORDANCE WITH THE INSTITUTE OF INSPECTION, CLEANING AND RESTORATION CERTIFICATION (IICRC) S500

| | | | | |
|---|---|---|---|---|
| TTI Environmental, Inc.<br>www.ttienv.com | WILLIAM PATERSON UNIVERSITY<br>HUNZIKER HALL BASEMENT<br>300 Pompton Road, Wayne, NJ | SCALE<br>NTS | DRAWN BY<br>DC | DATE<br>09/2015 |
| | | PROJECT<br>14-1532 | APP'D BY<br>JS | DRAWING NO.<br>ASB-4 |